

09/869131

JC03 R

PCT/PTC

25 JUN 2001

PATENTS

## IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

Applicant: Claude FELL

Serial No.: Not yet assigned -  
(National phase of International  
Application No. PCT/IB99/02053 filed December 24, 1999;  
claiming priority of PCT/IB98/02114 filed December 24, 1998)

Filed: (on even date herewith)

For: **BLOOD SEPARATION SYSTEM PARTICULARLY FOR  
CONCENTRATING HEMATOPOIETIC STEM CELLS**CLAIM OF PRIORITY UNDER 35 U.S.C. 119

Assistant Commissioner for Patents  
Washington, D.C. 20231

Dear Sir:

A formal claim for the benefit of priority of the filing date of December 24, 1998 of prior International Patent Application PCT/IB98/02114 filed December 24, 1998, as required by 37 C.F.R. 1.63, is hereby requested for the above-identified application.

Acknowledgment of this Claim of Priority by the Examiner and/or the Office in the next official communication mailed from the U.S. Patent and Trademark Office, is respectfully requested.

Respectfully submitted,

Claude FELL

Date

HENDERSON & STURM LLP  
206 Sixth Avenue, Suite 1213  
Des Moines, Iowa 50309-4076  
Telephone: (202) 296-3854  
Telefax: (202) 223-9606

By:

*Thomas J. Oppold*  
Thomas J. Oppold  
Reg. No. 42,054

**EXPRESS MAIL CERTIFICATE**

No. EL219226 CCJUS  
I hereby certify that this paper or fee is being  
deposited with the U.S. Postal Service using  
"Express Mail-Post Office to Addressee"  
service under 37 CFR 1.10 and addressed to the  
Commissioner of Patents and Trademarks,  
Washington, D.C. 20231 on June 25, 2001  
*Thomas J. Oppold*



9/809/31



RE	29 DEC 1999
WIPO	PCT

PCT/1B99/02053

**WORLD INTELLECTUAL PROPERTY ORGANIZATION  
ORGANISATION MONDIALE DE LA PROPRIÉTÉ INTELLECTUELLE**

34, chemin des Colombettes, Case postale 18, CH-1211 Genève 20 (Suisse)  
Téléphone: (41 22) 338 91 11 - e-mail: wipo.mail @ wipo.int. - Fac-similé: (41 22) 733 54 28

**PATENT COOPERATION TREATY (PCT)  
TRAITÉ DE COOPÉRATION EN MATIÈRE DE BREVETS (PCT)**

**CERTIFIED COPY OF THE INTERNATIONAL APPLICATION AS FILED  
AND OF ANY CORRECTIONS THERETO**

**COPIE CERTIFIÉE CONFORME DE LA DEMANDE INTERNATIONALE, TELLE QU'ELLE  
A ÉTÉ DÉPOSÉE, AINSI QUE DE TOUTES CORRECTIONS Y RELATIVES**

International Application No. } Demande internationale n° }	PCT / 1B 99 / 02053	International Filing Date } Date du dépôt international }	24 DECEMBER 1999 (20.12.99)
--	---------------------	--	--------------------------------


Geneva/Genève,

20 DECEMBER 1999  
(20.12.99)

**International Bureau of the  
World Intellectual Property Organization (WIPO)**

**Bureau International de l'Organisation Mondiale  
de la Propriété Intellectuelle (OMPI)**

**PRIORITY  
DOCUMENT**  
SUBMITTED OR TRANSMITTED IN  
COMPLIANCE WITH RULE 17.1(a) OR (b)



J.-L. Baron  
Head, PCT Receiving Office Section  
Chef de la section "office récepteur du PCT"

PCT

## REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

PCT / IB 98 / 02114

International Application No.

24 DECEMBER 1998

(24.12.98)

International Filing Date

INTERNATIONAL BUREAU OF WIPO

PCT International Application

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference

(if desired) (12 characters maximum)

F7.203 / PCTX

## Box No. I TITLE OF INVENTION

Blood Separation System Particularly for Concentrating Hematopoietic Stem Cells

## Box No. II APPLICANT

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

BIOSAFE S.A.  
Rue de l'Aiselet  
1262 Eysins

☐ This person is also inventor.

Telephone No.

Facsimile No.

Teleprinter No.

State (that is, country) of nationality:

Switzerland

State (that is, country) of residence:

Switzerland

This person is applicant for the purposes of:

☐ all designated States

☒ all designated States except the United States of America

☐ the United States of America only

☐ the States indicated in the Supplemental Box

## Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

FELL Claude  
Rte du Stand 22  
1260 Nyon

This person is:

☐ applicant only

☒ applicant and inventor

☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

Switzerland

State (that is, country) of residence:

Switzerland

This person is applicant for the purposes of:

☐ all designated States

☐ all designated States except the United States of America

☒ the United States of America only

☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on a continuation sheet.

## Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:

☒ agent

☐ common representative

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

Brian Cronin  
Moinas Savoye & Cronin  
42, rue Plantamour  
1201 Geneva  
Switzerland

Telephone No.

+41 22 731 93 56

Facsimile No.

+41 22 73870 56

Teleprinter No.

☐ Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

## Box No.V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

## Regional Patent

- ☐ AP ARIPO Patent: GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SZ Swaziland, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☐ EA Eurasian Patent: AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☐ EP European Patent: AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☐ OA OAPI Patent: BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)

## National Patent (if other kind of protection or treatment desired, specify on dotted line):

- |  |  |
|--|--|
| <input checked="" type="checkbox"/> AL Albania                               | <input checked="" type="checkbox"/> LS Lesotho                                   |
| <input checked="" type="checkbox"/> AM Armenia                               | <input checked="" type="checkbox"/> LT Lithuania                                 |
| <input checked="" type="checkbox"/> AT Austria                               | <input checked="" type="checkbox"/> LU Luxembourg                                |
| <input checked="" type="checkbox"/> AU Australia                             | <input checked="" type="checkbox"/> LV Latvia                                    |
| <input checked="" type="checkbox"/> AZ Azerbaijan                            | <input checked="" type="checkbox"/> MD Republic of Moldova                       |
| <input checked="" type="checkbox"/> BA Bosnia and Herzegovina                | <input checked="" type="checkbox"/> MG Madagascar                                |
| <input checked="" type="checkbox"/> BB Barbados                              | <input checked="" type="checkbox"/> MK The former Yugoslav Republic of Macedonia |
| <input checked="" type="checkbox"/> BG Bulgaria                              |  |
| <input checked="" type="checkbox"/> BR Brazil                                | <input checked="" type="checkbox"/> MN Mongolia                                  |
| <input checked="" type="checkbox"/> BY Belarus                               | <input checked="" type="checkbox"/> MW Malawi                                    |
| <input checked="" type="checkbox"/> CA Canada                                | <input checked="" type="checkbox"/> MX Mexico                                    |
| <input checked="" type="checkbox"/> CH and LI Switzerland and Liechtenstein  | <input checked="" type="checkbox"/> NO Norway                                    |
| <input checked="" type="checkbox"/> CN China                                 | <input checked="" type="checkbox"/> NZ New Zealand                               |
| <input checked="" type="checkbox"/> CU Cuba                                  | <input checked="" type="checkbox"/> PL Poland                                    |
| <input checked="" type="checkbox"/> CZ Czech Republic                        | <input checked="" type="checkbox"/> PT Portugal                                  |
| <input checked="" type="checkbox"/> DE Germany                               | <input checked="" type="checkbox"/> RO Romania                                   |
| <input checked="" type="checkbox"/> DK Denmark                               | <input checked="" type="checkbox"/> RU Russian Federation                        |
| <input checked="" type="checkbox"/> EE Estonia                               | <input checked="" type="checkbox"/> SD Sudan                                     |
| <input checked="" type="checkbox"/> ES Spain                                 | <input checked="" type="checkbox"/> SE Sweden                                    |
| <input checked="" type="checkbox"/> FI Finland                               | <input checked="" type="checkbox"/> SG Singapore                                 |
| <input checked="" type="checkbox"/> GB United Kingdom                        | <input checked="" type="checkbox"/> SI Slovenia                                  |
| <input checked="" type="checkbox"/> GE Georgia                               | <input checked="" type="checkbox"/> SK Slovakia                                  |
| <input checked="" type="checkbox"/> GH Ghana                                 | <input checked="" type="checkbox"/> SL Sierra Leone                              |
| <input checked="" type="checkbox"/> GM Gambia                                | <input checked="" type="checkbox"/> TJ Tajikistan                                |
| <input checked="" type="checkbox"/> GW Guinea-Bissau                         | <input checked="" type="checkbox"/> TM Turkmenistan                              |
| <input checked="" type="checkbox"/> HR Croatia                               | <input checked="" type="checkbox"/> TR Turkey                                    |
| <input checked="" type="checkbox"/> HU Hungary                               | <input checked="" type="checkbox"/> TT Trinidad and Tobago                       |
| <input checked="" type="checkbox"/> ID Indonesia                             | <input checked="" type="checkbox"/> UA Ukraine                                   |
| <input checked="" type="checkbox"/> IL Israel                                | <input checked="" type="checkbox"/> UG Uganda                                    |
| <input checked="" type="checkbox"/> IS Iceland                               | <input checked="" type="checkbox"/> US United States of America                  |
| <input checked="" type="checkbox"/> JP Japan                                 |  |
| <input checked="" type="checkbox"/> KE Kenya                                 | <input checked="" type="checkbox"/> UZ Uzbekistan                                |
| <input checked="" type="checkbox"/> KG Kyrgyzstan                            | <input checked="" type="checkbox"/> VN Viet Nam                                  |
| <input checked="" type="checkbox"/> KP Democratic People's Republic of Korea | <input checked="" type="checkbox"/> YU Yugoslavia                                |
|  | <input checked="" type="checkbox"/> ZW Zimbabwe                                  |
| <input checked="" type="checkbox"/> KR Republic of Korea                     |  |
| <input checked="" type="checkbox"/> KZ Kazakhstan                            |  |
| <input checked="" type="checkbox"/> LC Saint Lucia                           |  |
| <input checked="" type="checkbox"/> LK Sri Lanka                             |  |
| <input checked="" type="checkbox"/> LR Liberia                               |  |

Check-boxes reserved for designating States (for the purposes of a national patent) which have become party to the PCT after issuance of this sheet:

- ☒ IN India
- ☒ GD Grenada

**Precautionary Designation Statement:** In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)

Box No. VI PRIORITY CLAIM		<input type="checkbox"/> Further priority claims are indicated in the Supplemental Box.		
Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		national application: country	regional application: regional Office	international application: receiving Office
item (1)				
item (2)				
item (3)				

☐ The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office) identified above as item(s):

\* Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.

## Box No. VII INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA) (if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):	Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):		
ISA /	Date (day/month/year)	Number	Country (or regional Office)

## Box No. VIII CHECK LIST; LANGUAGE OF FILING

This international application contains the following number of sheets: request : 3 description (excluding sequence listing part) : 16 17 claims : 4 5 abstract : 1 drawings : 7 sequence listing part of description : 1 Total number of sheets : 32 34	This international application is accompanied by the item(s) marked below: 1. <input type="checkbox"/> fee calculation sheet 2. <input type="checkbox"/> separate signed power of attorney 3. <input checked="" type="checkbox"/> copy of general power of attorney; reference number, if any: X 2 4. <input type="checkbox"/> statement explaining lack of signature 5. <input type="checkbox"/> priority document(s) identified in Box No. VI as item(s): 6. <input type="checkbox"/> translation of international application into (language): 7. <input type="checkbox"/> separate indications concerning deposited microorganism or other biological material 8. <input type="checkbox"/> nucleotide and/or amino acid sequence listing in computer readable form 9. <input type="checkbox"/> other (specify):
---	--

Figure of the drawings which should accompany the abstract: Fig. 2	Language of filing of the international application: English
--	--

## Box No. IX SIGNATURE OF APPLICANT OR AGENT

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).

*Kuan Lin*  
AGENT

For receiving Office use only		2. Drawings:  <input type="checkbox"/> received:  <input type="checkbox"/> not received:
1. Date of actual receipt of the purported international application: 24 DECEMBER 1998	(24. 12. 98)	
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:		
4. Date of timely receipt of the required corrections under PCT Article 11(2):		
5. International Searching Authority (if two or more are competent): ISA /	6. <input checked="" type="checkbox"/> Transmittal of search copy delayed until search fee is paid.	

For International Bureau use only

Date of receipt of the record copy  
by the International Bureau:

Blood Separation System Particularly for Concentrating  
Hematopoietic Stem Cells

FIELD OF THE INVENTION

5        This invention relates to the automated processing  
and separation of biological cells as found in whole  
blood, and relates more specifically to a functionally  
closed system allowing to extract certain cell populations  
like hematopoietic stem cells, for immediate use or their  
10       mixing with an additive solution or a storage solution for  
later separate storage operations and to the methods for  
carrying such an extraction.

BACKGROUND OF THE INVENTION

15       Blood separation systems and methods have emerged  
over the past 20 years in response to the growing need for  
efficient blood component therapies. Among them are the  
transplantation of hematopoietic progenitor stem cells,  
which in many cases is the only remaining cure to  
20       oncological disorders. Patients in need of a stem cell  
transplant have mainly three options:

- 1) Adult bone marrow stem cells;
- 2) Peripheral blood stem cells found in the  
circulatory system;
- 25       3) Stem cells found in umbilical cord and placental  
blood retrieved at birth of a new born infant.

For most stem cell transplants, the limitations have  
been the risk of graft-versus-host-disease (GVHD),  
requiring an excellent HLA-match tissue (HLA = Human  
30       Leucyte Associated).

- 2 -

Umbilical cord blood is a rich source of the primitive hematopoietic stem and progenitor cells, with extensive proliferation capacity and capacity to self-renew. This field has advanced rapidly from clinical implants utilizing only HLA-matched grafts to unrelated donor cell transplants which open a much larger indication for stem cell transplantation. This increase in clinical experience with cord blood is due mainly to the banks for storage of hematopoietic stem cells from unrelated umbilical blood cord.

Blood volumes recovered from umbilical cord are usually very low (40 to 150 ml) and there is some concern that any attempt at product manipulation and concentration might result in stem cell loss, which might impair engraftments. Therefore umbilical cord blood is sometimes stored as is, with preservative solution added. A much preferred way would be to eliminate most unwanted cells like red cells and white cells, resulting in a considerable volume reduction. Less preservative solution would be required, smaller bags, smaller storage spaces would be used and considerable energy savings achieved, all of this translating in substantial cost savings. The quality of the stem cell product when retransfused would be improved as well, as lysed cells resulting from storage would be drastically reduced.

No device or automated system exists for processing and concentrating on line umbilical cord stem cells. There is nevertheless a considerable interest for concentrating umbilical cord blood stem cells without loss or altering their functionality.

WO 97/15399 (C.FELL), the contents whereof are herein incorporated by way of reference, describes a system for the processing and separation of biological fluids into components, comprising a set of containers for receiving



the biological fluid to be separated and the separated components, and optionally one or more additional containers for additive solutions. A hollow centrifugal processing chamber is rotatable about an axis of rotation and has an axial inlet/outlet for the biological fluid to be processed and for the processed components of the fluid. The processing chamber contains a movable member such as a piston which defines a separation space of variable size for receiving biological fluid, the piston being movable to intake a selected quantity of biological fluid to be processed into the separation space via said inlet and to express processed biological fluid components from the separation space via said outlet. Means are provided for monitoring the position of the movable member to thereby control the amount of intaken biological fluid and the expression of separated components. The system further comprises a distribution valve arrangement for establishing selective communication between the processing chamber and selected containers or for placing the processing chamber and containers out of communication.

The system according to WO 97/15399 is designed to operate for the separation of biological fluids, and has proven to be very polyvalent for many separation applications, especially for on-line separation of components from a donor or a patient.

#### DISCLOSURE OF THE INVENTION

According to the invention, such system is arranged to operate in a separation mode and in a non-separation transfer mode, which provides greater possibilities for use of the system including new applications which were heretofore not contemplated, such as separation of hematopoietic stem cells and in general laboratory

processing. According to the invention, the system is arranged to operate such that:

5       - in the separation mode fluids can be intaken into the processing chamber while the chamber is rotating or stationary, fluid intaken into the chamber is centrifuged and separated into components, and the separated components expressed while the chamber is rotating or, optionally, for the last separated component, while the chamber is stationary; and

10       - in the transfer mode the processing chamber intakes fluid and expresses fluid with the chamber stationary. The valve actuation arrangement is actuatable to transfer amounts of fluid from one container to another via the processing chamber, by moving the piston, without  
15       centrifugation or separation of the fluid into components, and the means for monitoring the position of the piston controls the amounts of non-separated fluids transferred.

20       Further features of the invention are set out in the claims. This invention thus proposes a functionally closed processing kit associated with a portable apparatus, whose function is to monitor and automate the procedure. The kit, usually disposable for avoiding the likelihood of disease transmission, is based on a centrifugal processing chamber whose volume can be varied during operation,  
25       allowing to adjust to the exact quantity of blood to process. Such variable volume chamber is described in the aforementioned WO 97/15399 (C.FELL). The chamber is connected to a set of bags and tubing lines for the collection of the separated components. The blood bag  
30       containing the blood to process is generally connected to the disposable set through the use of a sterile connecting device. It is however possible to have this bag preconnected to the disposable kit.

A bag containing an additive solution can be connected to the disposable kit via a bacterial filter. The other bags are provided for the collection of the separated components. The stem cell collection bag material is optimally chosen for the storage conditions.

The tubing line selection for conveying the separated products into the proper bags is accomplished by a set of rotational valves called stopcocks that can be arranged in a manifold array, or by a single multiport rotational valve, forming part of the set. Such an arrangement allows to eliminate any cross-contamination between adjacent lines when using standard pinch valves.

The above-mentioned disposable kit cooperates with an instrumentation for monitoring and automating the process, for instance as described in WO 97/15399 (C.FELL). The centrifuge drives a rotating disk which cooperates with the centrifugal processing chamber and locks it in place. Its closing cover will grip and hold the housing of the rotary seal of the processing chamber.

An optical sensor made of an array of LED and corresponding receiving sensors placed at  $180^\circ$  is implemented vertically on the side of centrifuge, for monitoring the piston position. Volume intaken into or extracted from the chamber can therefore be exactly measured. The topdeck receives an optical line sensor module which monitors the color in the effluent tubing, feeding-back this information to the control program. An array of shafts equipped with fittings for driving a set of multiple stopcocks valves protrude from the top deck. They are coupled to a set of motors enabling the tubing line selection. Encoders are attached to the motors for monitoring the stopcock valves position. The front panel incorporates a window allowing the user to see displacement of the piston in the chamber.

The procedure for extracting stem cells out of an umbilical cord is as follows. Initially blood is recovered from the umbilical cord at birth and collected aseptically into a plastic bag, with anticoagulant added like Citrate-Phosphate-Dextrose CPD-1 to avoid clotting. After initial sampling is taken to assess the its richness in stem cells, the bag is sterile connected to the processing kit and the whole set is loaded onto the separation system. The centrifuge starts driving the separation chamber at around 4000 rpm, and blood is introduced by moving down the chamber piston pneumatically. Two cases can then occur. If the volume of blood to process is smaller than the processing chamber volume (as detected by the empty state of the effluent tubing), the piston is maintained at an intermediate position pneumatically, monitored by the piston position sensor. If the volume of blood completely fills the separation chamber, detected by the piston reaching the bottom of the chamber, the pneumatic compressor stops. In both cases, centrifugation speed is increased to around 6000 rpm to shorten the sedimentation time to 2-3 min. After this period, centrifugation slowly decreases to around 4000 rpm. Stopcocks are rotated to allow the collection of the separated products, and the pneumatic pressure gradually increases to move the piston upwards. The speed of the piston remains low, actively monitored by the piston position sensor, in order to maintain the sedimentation profile of the cells within the chamber. The first product extracted is plasma, collected into a first bag. It is followed by platelets, packed in the intermediate layers, or buffy-coat. Apparition of the first platelets is detected by the optical line sensor monitoring the effluent line tubing. At that moment, the product, very rich in stem cells, is directed into a second collection bag by rotating a stopcock valve. A volume counter is started, which depends among other factors on the total blood volume processed. When this

counting volume has been reached, centrifugation is stopped. The proper stopcock valve is rotated and the last product is extracted, essentially a volume of packed red cells with residual granulocytes, into a third collection bag. Another cycle can then resume if the umbilical cord blood has not been totally processed. Otherwise, the separation and stem cells collection process is completed at this stage. Adequate preservative solution is introduced into the processing chamber by rotating the proper stopcock. It is then retransferred into the stem cell bag, its volume accurately controlled by the piston position sensor.

The bag containing the stem cell rich product can be disconnected at this stage from the rest of the set. Its volume ranges between 20-40 ml, depending of the initial volume processed. The by-products of the separation, plasma and packed red cells, can then be used for serology and HLA typing, avoiding any product loss due to sampling in the stem cell bag.

This separation system and method offer significant advantages over manual processing techniques. The disposable kit is a functionally closed system, avoiding any risk of contaminating the product during manipulation. The protocol is fully automated, through a microprocessor based control system, with ability to vary the main parameters, like centrifugation speed, centrifugation time, speed of introduction and extraction, volume to collect, etc. The volume reduction for the stem cell product represents a gain of 50% at least compared with the current state of the art. The instrumentation is very compact and portable, ideal for the decentralized processing of such procedures.

## BRIEF DESCRIPTION OF THE DRAWINGS

The invention will be further described by way of example with reference to the accompanying drawings in which:

5       - Fig. 1 is a schematic side elevation and cross-sectional view of a processing chamber and its rotary seal, showing the various sedimentation layers of blood components.

10       - Fig. 2 is a schematic side elevation and cross-sectional view of the processing chamber and its rotary seal, associated with an optical sensor for monitoring the piston sensor, and control circuitry.

15       - Fig. 3 illustrates in a schematic form the disposable set carrying a manifold stopcock system for the processing and separation of umbilical cord blood.

      - Fig. 4 illustrates in a schematic form an array of stopcocks arranged in a manifold.

20       - Fig. 5 is a schematic side elevation and cross-sectional view of the motor driver and control elements for rotating each individual stopcock.

      - Fig. 6 is a schematic side elevation and cross-sectional view of a multiport rotational valve.

25       - Fig. 7 schematically illustrates the multiport rotational valve of Figure 6 with an inlet/outlet port located at the center and a range of associated ports located at the periphery.

      - Fig. 8 is perspective view of a cabinet containing instrumentation and devices for controlling the processing.

- Fig. 9. 1 to Fig. 9.6 are functional diagrams showing the various steps of umbilical cord blood separation using a disposable set including a processing chamber and a set of stopcocks according to the invention.

#### DETAILED DESCRIPTION OF THE SYSTEM

5

The processing chamber 20 is in accordance with that described in WO 97/15399 (C.FELL). Fig. 1 is a general view of the processing chamber 20. A rotary seal 12 is located on its upper extremity 10. The rotary seal 12 is composed of an upper body 1 and lower body 2. In between is located a friction disk 3, made of a generally low friction material like polished stainless steel or ceramic. A central tubing 7 made of biocompatible material like polycarbonate is attached to the upper body 1. An O-ring 8 ensures airtightness between the upper body 2 and friction disk 3. The rotary seal 12 is mounted on a central bush 11 fitted on the upper extremity 10 of processing chamber 20. The gap between walls of central tubing 7 and central bush 11 is small, say 0.5 mm, to provide a high rotational impedance for stopping any liquid to reach the upper extremity of bush 11. A ball bearing 9 is mounted on bush 11 to ensures the proper alignment of the processing chamber 20 when inserted into centrifuge assembly. Two rubber seals 5,6 are located on either side of the friction disk 3, seal 5 being on the upper side and seal 6 being on the lower side. The seals 5 and 6 are of the V-seal type and ensure airtightness both in positive and negative pressure, up to at least  $\pm 0.5$  bar.

30

The piston 21 is made of a transparent material like polycarbonate and is equipped with two O-rings 24 and 25. The processing chamber 20 is closed on its bottom side by a cap 22 carrying a bacterial filter 23. Air can pass through central opening 26 and filter 23 in cap 22. The

- 10 -

position of the piston 21 can be accurately monitored by an optical sensor assembly 60 and 61 (Fig 2). Assembly 61 is made of a vertical array of LED, preferably with light emitting in the infrared spectrum to reduce disturbance from ambient light. Only the LED facing piston 21 are  
5 turned on, in order to avoid interference from the other LED. The beam of light crosses the transparent piston 21, between the two O-rings 24 and 25. A CCD ("Charge Coupling Device") linear array 61 is placed at 180° on the other  
10 side, the exposed pixels of array 61 generating a signal 62 in the form of a peak.

Signal 62 is fed to a low-pass filter 69 and the filtered signal fed to a comparator 67 which also receives from potentiometer 68 a threshold value for discriminating  
15 the filtered signal from ambient noise. The output of comparator 67 is connected to the enable gate of counter 65. Clock signal 66 is used to intake the response from each individual pixel of the CCD linear array 61, and feed this to the input of counter 65. The output of counter 65  
20 is connected to a CPU 64 which calculates the position of piston 21 and, when required, shifts the turned-on LEDs 60 via a multiplexer/LED driver 63. Similarly, when necessary, the CPU 64 will vary the signal of compressor driver 70 that supplies compressor 71 in order to increase  
25 or decrease pressure applied below the piston 21 to control its position.

This is only one example of position sensing for the piston 21. The light source 60 could be a filament bulb, or a unique linear source of light. The CCD linear array  
30 61 could be replaced by an array of photosensing devices. The receiving sensing device (61) could be placed also beside the emitting light device 62, the system working in reflection light from the piston 61 rather in transmittance light through the piston 21.



The disposable set (Fig 3) is composed of bags 40-44, tubing lines connected to stopcocks 45-48, and the processing chamber 20. Bag 40 contains the umbilical cord blood to process. Bag 41 contains preservative solution, generally based on a DMSO (Dimethyl Sulfoxide) solution. It is connected to the disposable set through a bacterial 0.2 micron filter 54. Bag 42 is the collection bag for the stem-cell rich product. Its plastic composition is made of a material suiting long term storage. Bag 43 is the collection bag for the plasma and bag 44 is the one for the red cells.

An array of stopcocks 45-48 (Fig. 5) organized in a manifold 58 allows the connection between the different tubing lines. These rotational stopcocks provide an excellent cut-off between adjacent lines and ensure that no leak occurs between a closed and an open line, as is the case with tubing pinch valves. Such manifold stopcocks exist in various forms and are commercially available. The stopcocks 45-48 are driven by a set of motors 100-103. (Fig 6). The upper shafts 84-87 of these motors engage into the bottom portion of the respective stopcocks 45-48, using passing holes through the cabinet topdeck 88. The motors can be stepper motors or DC motors with reducers. They are equipped with position encoders 104-107, whose signals are fed back to the microprocessor control unit, ensuring that the stopcocks are correctly positioned.

An alternative to using a manifold stopcock is a rotational multiport valve, as shown in Figs. 6 and 7. A central rotor 127 is inserted into a stator 126. The rotor 127 can be frictionally rotated. The central port 120, connected to the processing chamber 20, can be connected to the peripheral ports 121-125 by rotation with angular steps of 72°. A single motor is necessary to drive the rotor through the engagement recess 132. Two O-rings 130-131 ensure watertightness with the exterior (Fig.6).

The cabinet holding the instrumentation is shown in Fig. 8. It contains the cover 94 for holding the rotary seal 12 of the processing chamber 20. The cover 94 is made of two semi-circular shells that can rotate on hinge 89. An optical line sensor 83 allows the sensing of colors in the effluent tubing 51. It holds two LED-Photosensor channels, of different wavelength like red and green, and is capable of detecting the first cells coming out of the chamber 20. It can equally detect the empty state of the effluent line tubing when liquid is introduced in the chamber. The pressure port measurement 86 receives the bacterial filter 49 located on the disposable set. This allows the monitoring of the pressure in the processing chamber 20. Upper shafts 84-87 of the stopcock driver motors 100-103 (Fig. 5) are located behind the line sensor 83. An inclined module 90 receives the display 82 for user information and a keyboard 81 for controlling the instrumentation. A window 91 is located on the front panel 92 giving visibility to the chamber piston movement.

#### Application for Umbilical Blood Separation

Figs. 9.1 to 9.6 illustrate an application for umbilical cord blood separation. Bag 40 contains the umbilical cord blood rich in stem cells, recovered from the umbilical cord at birth of a child.

This bag 40 contains anticoagulant like CPD to avoid blood clots. Tubing line 53 is sterily connected to line 52 using a sterile connecting device. However it is also possible to have the bag 40 preconnected to the whole set. The separation steps are:

**Step 1** (Fig 9.1): Stopcocks 45 and 46 are rotated to connect bag 40 to the processing chamber 20. Centrifugation starts and initially is stabilized at a speed of 4000 rpm. The pneumatic system of the instrumentation establishes a vacuum to move the piston 21

downwards. Its speed is monitored by the optical sensor assembly 61 and 62, and the vacuum level is adjusted accordingly. If the volume of the bag 40 is smaller than the processing volume of chamber 20, effluent tubing line 51 will empty, which is detected by the optical line sensor 83. The piston 21 is maintained motionless by establishing a counter pressure through the pneumatic system, and the volume intaken into chamber 20 is recorded. The centrifuge speed is gradually increased to reach 6000 rpm, with pressure increased accordingly to keep piston 21 at the same position. In the case where the volume of bag 40 is larger than the processing volume of chamber 20, piston 21 will reach the bottom of the chamber, and the pneumatic system is turned off. In both cases, after a sedimentation time of about 2-3 min, centrifuge speed is slowly decreased, while maintaining a constant counter pressure below piston 21. Stopcocks 46, 47, 48 are rotated to establish a path between the processing chamber 20 and the plasma bag 43.

**Step 2** (Fig. 9.2): When the centrifuge drops to a speed generally around 4000 rpm, the piston 21 starts to move upwards, with a preset speed allowing extraction rates around 100 ml/min. This value can be modified through the program parameters. Plasma starts to be collected in bag 43. When the volume of plasma extracted reaches approximately 40% of the volume intaken, the extraction rate will be reduced by half. The first platelets contained in the buffy-coat layer start to be extracted, which is detected by light absorbance in the optical line sensor 83. At a certain level of absorbance, which can be parametered by the control program, stopcock 47 is rotated to establish the path between the processing chamber 20 and bag 42.

**Step 3** (Fig 9.3): A volume counter is triggered, and collection of a product very rich in stem cells starts.

- 14 -

Extraction speed is always under the control of the piston optical sensor assembly 61 and 62. The volume counter value can be altered by the user in the program menu. It is chosen in order to encompass all the stem cell population, which has similar characteristics in density and size to the lymphocyte population. Such value corresponds generally to 20-30% of the intaken volume into the chamber. When this value is reached, stopcocks 47 and 48 are rotated to establish a path with bag 44.

10       **Step 4** (Fig. 9.4): Centrifugation is generally stopped at this stage, and pressure diminished to allow a smooth extraction of the remaining red cells into bag 44. This phase is completed when piston 21 reaches the top of the processing chamber 20, detected by the piston optical sensor assembly 61 and 62. At this stage, if the bag 40 is not empty, the process will be resumed at Step 1, otherwise it will proceed with Step 5. An optional phase is to further separate the stem cell product by returning the content of bag 42 into the processing chamber 20, centrifuging the product once again and expressing its separated components to bags 43, 42 and 44 as before.

25       **Step 5** (Fig. 9.5): Stopcocks 45 and 46 are rotated in order to establish a path between the preservative solution bag 41 and the processing chamber 20. The preservative solution is generally a composition based on 10 or 20vol% DMSO chemical solution, which can contain also a phosphate buffer. The centrifuge being idle, piston 21 is moved downwards by establishing a vacuum with the pneumatic system. The volume intaken is a proportion of the volume counter described in Step 4. When this proportion is reached the vacuum stops and stopcocks 46 and 47 are rotated in order to establish a path between the processing chamber 20 and the stem cell bag 42.

**Step 6** (Fig. 9.6): The pneumatic system is turned down, and piston 21 moved upwards. The preservative solution is added to the content of the stem cell bag 42. This phase is completed when the piston reaches the top of the processing chamber 20, detected by the piston optical sensor assembly 61 and 62. An optional additional phase can be added if the stem cell product needs to be diluted further with plasma. In this case Steps 5 and 6 will be repeated, with the difference that the transfer will be established between the plasma bag 43, the processing chamber 20 and the stem cell bag 42.

When all the steps described above are completed, all the stopcocks can be rotated at a 45° angle in order to close all the communicating ports. The bags 42-44 can be disconnected from the rest of the set, which can be discarded at this stage. The stem cell bag 42 is then ready for conveying to a separate storage unit, the by-products plasma in bag 43 and red cells 44 being used for HLA typing and quality control assessments.

It is to be understood that this invention may be embodied in several different forms without departing from its spirit of essential characteristics. The scope of the invention is defined in the appended claims, rather than in the specific description preceding them. All embodiments that fall within the meaning and range of equivalency of the claims are therefore intended to be embraced by the claims.

Moreover, the novel optical control device (60-71) herein described, as well as the arrangement of stopcocks (45-48) and tubing, the multiport valve (Fig. 6 and 7), the special rotatable seal (1-7) for positive and negative pressure operation, and the special axial bearings mounting the chamber 20, permitting drive without a

- 16 -

holding chuck, can all advantageously be used in different systems.

## CLAIMS

1. A system for the processing and separation of biological fluids into components, comprising a set of containers (40,42-44) for receiving the biological fluid to be separated and the separated components, and optionally one or more additional containers (41) for additive solutions, and a hollow centrifugal processing chamber (20) rotatable about an axis of rotation and having an axial inlet/outlet (7) for the biological fluid to be processed and for the processed components of the fluid, the processing chamber containing a movable member (21) which defines a separation space of variable size for receiving biological fluid, the member (21) being movable to intake a selected quantity of biological fluid to be processed into the separation space via said inlet and to express processed biological fluid components from the separation space via said outlet, and means (60-69) for monitoring the position of the movable member (21) to thereby control the amount of intaken biological fluid and the expression of separated components, the system further comprising a distribution valve arrangement (45-48;120-127) for establishing selective communication between the processing chamber (20) and selected containers (40-44) or for placing the processing chamber and containers out of communication, the system being arranged to operate in a separation mode and in a non-separation transfer mode, wherein:

- in the separation mode fluids can be intaken into the processing chamber (20) while the chamber is rotating or stationary, fluid intaken into the chamber is centrifuged and separated into components, and the separated components expressed while the chamber is rotating or, optionally, for the last separated component, while the chamber is stationary; and

- 18 -

- in the transfer mode the processing chamber (20) intakes fluid and expresses fluid with the chamber stationary, the valve actuation arrangement (45-48;120-127) being actuatable to transfer amounts of fluid from one container (40-44) to another via the processing chamber (20), by moving the piston, without centrifugation or separation of the fluid into components, and said means (60-69) for monitoring the position of the piston (21) controls the amounts of non-separated fluids transferred.

10        2. The system of claim 1, wherein the distribution valve arrangement comprises a plurality of stopcock valves (45-48) connected to tubing lines interconnecting the set of containers (40,42-44), the optional additional containers (41), the processing chamber (20) and further  
15 stopcock valves, each stopcock valve (45-48) comprising a rotatable stopcock valve member having a shaft (84-87) associated with drive means (100-103), the rotation of said shaft selectively connecting or disconnecting the stopcock valve's tubing lines.

20        3. The system of claim 1, wherein the distribution valve arrangement comprises a multiport valve comprising a central rotor (127) rotatably mounted in an annular stator (126), the rotor having a central port (120) connected to the processing chamber (20) and leading to the rotor outer  
25 periphery, and the stator having a plurality of ports (121-125) at selected angular locations each connected to a container (40-44) and each leading into the inner periphery of the annular stator, the central port (120) of the rotor being connectable to selected ports (121-125) of  
30 the stator (126), or disconnected, by rotation of the rotor (127).

4. The system of any preceding claim, wherein the movable member is a piston (21) fluid-tightly movably



mounted in a generally-cylindrical centrifugal processing chamber (20).

5        5. The system of claim 5, further comprising optical means for monitoring the position of the piston (21), comprising an alignment of light emitting elements (60) generally parallel to the piston axis, and an alignment of light receiving elements (61) generally parallel to the piston axis, the receiving elements (61) being arranged to receive light from the emitting elements (60) transmitted through or past the piston (21) or  
10       reflected by the piston (21), and delivering a signal (62) representative of the piston's position.

6. The system of claim 5, wherein said signal (62) is delivered to means (70,71) for moving the piston (21) and means (60-65) for controlling the piston's position.  
15

7. The system of any preceding claim, wherein the axial inlet/outlet comprises a rotatable seal (3-6) mountable in a stationary housing (1-2), said seal being operable for positive and negative pressure conditions in the rotatable chamber (20).  
20

8. The system of any preceding claim, wherein the processing chamber (20) is mounted for rotation about its axis by means of bearings (9; 72, 73) at opposite ends of the chamber, one end of the chamber (20) being associated with means (55-57) for rotating the chamber (20) without any support at the chamber periphery.  
25

9. A method of processing and separating biological fluids in a system according to any preceding claim, the method comprising:

30       separating a biological fluid with the system operating in the separation mode, by intaking fluid into the processing chamber (20) while the chamber is rotating

or stationary, centrifuging fluid intaken into the chamber (20) to separate the fluid into components, and expressing the separated components while the chamber is rotating or possibly, for the last component, while the chamber is stationary; and

transferring fluid between containers (40-44) with the system operating in the transfer mode, by intaking fluid into the processing chamber (20) with the chamber stationary, actuating the valve distribution arrangement (45-48;120-127) to transfer an amount of fluid from one container (40-44) to another via the processing chamber (20), by moving the member (21), without centrifugation or separation of the fluid into components, and monitoring the position of the movable member (21) to control the amount of non-separated fluid transferred.

10. The method of claim 9, wherein a component of the biological fluid is separated into a given container (42), the amount of said component separated into the given container (42) being controlled by monitoring the position of said member (21), and an additive solution is transferred from an additional container (41) to said given container (42) via the processing chamber (20) in said transfer mode, the amount of additive solution transferred being calculated as a function of the amount of said separated component in the given container (42).

11. A disposable set for collecting and separating selected quantities of biological fluids comprising the centrifugal processing chamber (20) of a system according to any one of claims 1 to 8, wherein the inlet/outlet of the centrifugal processing chamber (20) is connected to a container (40) of biological fluid, an additional container (41) containing an additive solution, a plurality of containers (42-44) for receiving the separated components of the biological fluid,

interconnected by a plurality of stopcock valves as defined in claim 2 or by a multiport valve as defined in claim 3.

5        12. Use of the system of any one of claims 1 to 8, for processing variable volumes of biological fluid from 10 ml up to the maximum volume of the separation chamber (20), and for adding an additive liquid to the separated components.

10       13. Use according to claim 12 for separation of stem cells from blood and mixing the separated stem cells with a preservative solution.

14. Use according to claims 12, for separation of hematopoietic stem cells from umbilical cord blood.

## ABSTRACT

A system for separating biological fluids into components, comprises a set of containers (40,42-44) for the biological fluid to be separated and the separated components, optionally an additional container (41) for additive solution, and a hollow centrifugal processing chamber (20) having an axial inlet/outlet (7) for the biological fluid. The processing chamber contains a piston (21) movable to intake a selected quantity of biological fluid and express processed biological fluid components via the outlet. Optical means (60-69) monitor the position of piston (21) to control the amount of intaken fluid and the expression of components. A distribution valve arrangement (45-48;120-127) selectively communicates the processing chamber (20) and the containers (40-44) or places them out of communication. The system is arranged to operate in a separation mode and in a non-separation transfer mode, especially for adding preservative solution to separated blood stem cells. In the separation mode, fluids are intaken into processing chamber (20), centrifuged and separated into components, and the components expressed. In the transfer mode, the processing chamber (20) intakes and expresses fluid with the chamber stationary, the valve actuation arrangement (45-48;120-127) transferring fluid from one container (40-44) to another via the processing chamber (20), by movement of the piston (21), without centrifugation or separation, and the means (60-69) for monitoring the piston's position controls the amounts of non-separated fluids transferred.

Legend

1	Upper body rotary seal	64	CPU system
2	Lower body rotary seal	65	Counter
3	Friction disk	66	Clock signal
4	Gap opening	67	Comparator
5	Upper V-seal	68	Potentiometer
6	Lower V-seal	69	Filter
7	Central tubing	70	Compressor driver
8	O-ring	71	Compressor
9	Ball-bearing	72	Lower bearing # 1
10	Upper extremity processing chamber	73	Lower bearing #2
11	Central axis	80	housing
12	Rotary seal	81	Keyboard
		82	Alphanumeric display
20	Processing chamber	83	Optical line sensor
21	Piston	84	Driving axis stopcock
22	Cap processing chamber	85	Driving axis stopcock
23	Bacterial filter	86	Driving axis stopcock
24	Piston upper O-ring	87	Driving axis stopcock
25	Piston lower O-ring	88	Housing topdeck
26	Chamber bottom central opening	89	Cover hinge
		90	Module user interface
30	Red cell layer	91	Front panel window
31	Stem cell layer	92	Front panel
32	Platelet layer	93	Pressure port
33	Plasma layer	94	Cover
		100	Motor
40	Umbilical cord blood bag	101	Motor
41	Cryopreservant solution bag	102	Motor
42	Stem cells bag	103	Motor
43	Plasma bag	104	Encoder
44	Red cell bag	105	Encoder
45	Stopcock	106	Encoder
46	Stopcock	107	Encoder
47	Stopcock	108	Motors support plate
48	Stopcock	109	
49	Pressure line pigtail	110	Motor support plate bolts
50	Bacterial filter		
51	Effluent line tubing	120	Chamber access port
52	Inlet tubing set pigtail	121	Umbilical cord blood access port
53	Outlet umbilical cord blood bag pigtail	122	Cryopreservant access port
54	Bacterial filter	123	Stem cell access port
55	Centrifuge rotating shaft	124	Plasma access port
56	Support plate	125	Red cell access port
57	Centrifuge motor	126	Multiport valve stator
58	Manifold support	127	Multiport valve rotor
60	Light emitting LED array		
61	Light receiving CCD linear array	130	Rotor upper O-ring
62	peak electrical signal pixels	131	Rotor lower O-ring
63	Multiplexor/LED driver	132	Rotor recess




Fig. 1




Fig. 2




Fig. 3






Fig. 4




Fig. 5




Fig. 6




Fig. 7




Fig. 8




Fig. 9.1




Fig. 9.2




Fig. 9.3




Fig. 9.4




Fig. 9.5




Fig. 9.6